

**OFFICE OF THE EXECUTIVE ENGINEER ELECTRICITY**  
**Operation Division Ghari Dupatta.**

To,

M/S Yousaf Ali Khan Sarder Govt. Contractor  
Abdual Tawab Khan Market Office #1 Sarder Bazar Charsadda KP.

**Subject: Work Order ADP Intensification of Power Distribution Network Of Electricity Department In North Region Of AJ&K 2019-20 (Package No.2) Sub Division Airport.**

With reference to the subject cited above that in response of advertisement No.1000 dated 26-11-2019 uploaded on AJK PPRA Website, your rates received on 12-12-2019 are found lowest and hereby sanctioned. It is therefore directed that you consult with the relevant SDO for getting Drawing and marking of area of site before the Commencing of work. The detail of work and sanctioned rates mentioned against them and conditions are given below.

Task	Discription of work			Unit	Qty	Unit Rate	Amount	
1	Installation of steel structure							
	Collection of HT Steel Structure with Earth Rod & Stay Set from Store Division Rampura Muzaffarabad, loading/unloading,Transportation, Safe handling of Steel Structure, Excavation, Erection, Concreting of Foundation, Curing, Backfilling with Hand Packed Stone as per WAPDA specification.	1.1	11 kV	HT Steel Structure(34.8')Long with ratio 1:3:6 Cement concrete size 2'x2'x6'.6" including Installation of Earth Rod.	No	7	10000	70000
		1.2	11 kV	Single Rod Stay Assembly with ratio 1:3:6 Cement concrete with wire	No	7	870	6090
		1.3	11 kV	X.Arms with Braces	No	10	350	3500
		1.4	11 kV	Disc Insulator complete	No	6	280	1680
		1.5	11 kV	Pin Insulator complete	No	18	180	3240
		1.6	11 kV	Rabbit Conductor	Km	2.17	5000	10850
2	Installation of steel structure							
	Collection of LT Steel Structure with Earth Rod & Stay Set fromStore Division Rampura Muzaffarabad, loading/unloading,Transportation, Safe handling of Steel Structure, Excavation, Erection, Concreting of Foundation, Curing, Backfilling with Hand Packed Stone as per WAPDA specification.	2.1	0.4kV	LT Steel Structure(31')Long with ratio 1:3:6 Cement concrete size 1'.8"x1'.8"x5'.6"	No	90	8500	765000
		2.2	0.4 kV	Single Rod Stay Assembly with ratio 1:3:6 Cement concrete	No	68	870	59160
		2.3	0.4kV	Ant Conductor (with all Hardware) Complete	Km	17.11	4000	68440
3	Installation of Transformers							
	Collection of material from Store Division Rampura Muzaffarabad, loading/unloading, Transportation, Safe handling,Installation together with connection to line including Earthing of T/F & Installation as per WAPDA specification.	3.1	50	KVA Transformer sub sation Complete (with all hardware)	No	1	11500	11500
	G.Total							999460

**Conditions :-**

- 1- Work must be completed upto 15-06-2020 according to above mentioned specifications.
- 2- Payment will be made after completion of work and dully verified/certified by sub Divisional officer.
- 3- 10% of total payable amount shall be released after maintenance period.
- 4- All admissible taxes shall be deducted from the bill at the time of payment.

Executive Engineer (E)

Operation Division MZD-II Gahri Dopatta

No. 130-133 Dated 05-01-2020

**Copy to;**

- 1 The Superintending Engineer Electricity Circle Muzaffarabad for Information.
- 2 Sub Divisional Officer **Airport** You are Directed to Visit the Site and Provide Progress to this Office Regarding the on
- 3 Divisional Account Officer Operation Division No.II Muzaffarabad (Garhi Dopatta).
- 4 Stoer Keeper Office of the Executive Engineer (E) Operation Division No II Muzaffarabad (Garhi Dopatta).

Executive Engineer (E)

Operation Division MZD-II Gahri Dopatta

**OFFICE OF THE EXECUTIVE ENGINEER ELECTRICITY**  
**Operation Division Ghari Dupatta.**

To,

M/S Galaxy Star Construction  
Govt. Contractor Muzaffarabad.

**Subject: Work Order ADP Intensification of Power Distribution Network Of Electricity Department In North Region Of AJ&K 2019-20 (Package No.1) Sub Division Garhi Dopatta.**

With reference to the subject cited above that in response of advertisement No.1000 dated 26-11-2019 uploaded on AJK PPRA Website, your rates received on 12-12-2019 are found lowest and hereby sanctioned. It is therefore directed that you consult with the relevant SDO for getting Drawing and marking of area of site before the Commencing of work. The detail of work and sanctioned rates mentioned against them and conditions are given below.

Task	Discription of work			Unit	Qty	Unit Rate	Amount
1	Installation of steel structure						
Collection of HT Steel Structure with Earth Rod & Stay Set from Store Division Rampura Muzaffarabad, loading/unloading,Transportation, Safe handling of Steel Structure, Excavation, Erection, Concreting of Foundation, Curing, Backfilling with Hand Packed Stone as per WAPDA specification.	1.1	11 kV	HT Steel Structure(34.8')Long with ratio 1:3:6 Cement concrete size 2'x2'x6'.6" including Installation of Earth Rod.	No	28	10000	280000
	1.2	11 kV	Single Rod Stay Assembly with ratio 1:3:6 Cement concrete with wire	No	35	870	30450
	1.3	11 kV	X.Arms with Braces	No	39	350	13650
	1.4	11 kV	Disc Insulator complete	No	36	280	10080
	1.5	11 kV	Pin Insulator complete	No	77	180	13860
	1.6	11 kV	Rabbit Conductor	Km	8.68	5000	43400
2	Installation of steel structure						
Collection of LT Steel Structure with Earth Rod & Stay Set fromStore Division Rampura Muzaffarabad, loading/unloading,Transportation, Safe handling of Steel Structure, Excavation, Erection, Concreting of Foundation, Curing, Backfilling with Hand Packed Stone as per WAPDA specification.	2.1	0.4kV	LT Steel Structure(31')Long with ratio 1:3:6 Cement concrete size 1'.8"x1'.8"x5'.6"	No	80	8500	680000
	2.2	0.4 kV	Single Rod Stay Assembly with ratio 1:3:6 Cement concrete	No	60	870	52200
	2.3	0.4kV	Ant Conductor (with all Hardware) Complete	Km	15.20	4000	60800
3	Installation of Transformers						
Collection of material from Store Division Rampura Muzaffarabad, loading/unloading, Transportation, Safe handling,Installation together with connection to line including Earthing of T/F & Installation as per WAPDA specification.	3.1	50	KVA Transformer sub sation Complete (with all hardware)	No	6	11500	69000
G.Total							1253440

**Conditions :-**

- 1- Work must be completed upto 15-06-2020 according to above mentioned specifications.
- 2- Payment will be made after completion of work and dully verified/certified by sub Divisional officer.
- 3- 10% of total payable amount shall be released after maintenance period.
- 4- All admissible taxes shall be deducted from the bill at the time of payment.

Executive Engineer (E)

Operation Division MZD-II Gahri Dopatta

No. 134-137 Dated 06-01-2020

**Copy to;**

- 1 The Superintending Engineer Electricity Circle Muzaffarabad for Information.
- 2 Sub Divisional Officer **Garhi Dopatta** You are Directed to Visit the Site and Provide Progress to this Office Regarding
- 3 Divisional Account Officer Operation Division No.II Muzaffarabad (Garhi Dopatta).
- 4 Storer Keeper Office of the Executive Engineer (E) Operation Division No.II Muzaffarabad (Garhi Dupatta)

Executive Engineer (E)

Operation Division MZD-II Gahri Dopatta