

OFFICE OF THE EXECUTIVE ENGINEER ELECTRICITY
OPERATION DIVISION ATHMUQAM

TO,

M.S Al Awan Neelum Construction Company
Muzaffarabad.

Subject: Work Order for Concreting of HT/LT Poles Stay Set & Fixing of Earthing Rod against S.O.P to Expansion of Power Distribution Network Cities /Towns.(Athmuqam H/Q).

With Reference on the Subject Sited above that in response of advertisement dated on 24-01-2020 your rates received on 12-02-2020 your rates are being found lowest are sanctioned. It is therefore directed to you that Consult with sub divisional officer for getting drawing and marking of area of site before the commencing of work. The detail of work and sectioned rates mentioned against and condition is given below.

Details:


S#	Description of Work	Units	Qty	Unit Rate	Total Amount	
1	Erection of HT/Lt Structure					
	Collection of material from Sub Divisional store transportation safe handling of Steel Structure / Excavation, Blasting, Erection, Concreting of foundation Curing Back filling & Concreting as per WAPDA Specification.	HT steel structures (34'.8") (1:3:6) Cement conc. 2'x2' x6'.6")	No.	25	9900	247500
		LT Steel Structures 21'Long with 1'.8"x1'.8"x5'.6" cement Conc. (1:3:6)	No.	32	7900	252800
2	Installation of Stay Set.					
	Collection of material Sub Divisional store, transportation safe handling, Excavation, installation/ Erection of Stay rod including connection with poles as per WAPDA Specification.	Single Rod stay assembly Complete with wire.	No.	52	600	31200
3	Installation of Earthing Rod.					
	Collection of material Sub Divisional store, transportation safe handling, Excavation, installation/ Erection of earthing rod including connection with poles as per WAPDA Specification.	Earthing Rod Complete for Line	NO.	25	350	8750
Total						540250

Conditions:

1. Work must be completed up to 30-06-2020 according to above mentioned specification.
2. Completion period will be start from the date of issuance of work order.
3. Payment will be made after completion of work dully verified/certified by Sub Engineer, Sub Divisional officer.
4. 10% of total payable amount as performance bound shall be released after maintenance period.
5. All admissible taxes shall be deducted from the bill at the time of payment.
6. Quantity of work/scope can be increased or decreased during the current financial year 2019-20 if required due to un avoidable circumstances.

No 602-06

Dated 27/02


Executive Engineer (E)
Operation Division Athmuqam

Copy to:

1. Superintending Engineer Electricity Circle Muzaffarabad for Information.
2. Sub Divisional Officer Electricity Athmuqam your are Directed to Visit the Site and Provide Progress to This as well as the completion of work within due date.
3. Divisional Account Officer Operation Division Athmuqam.
4. Store Keeper Operation Division Athmuqam.


Executive Engineer (E)
Operation Division Athmuqam