



THE DIRECTORATE GENERAL OF TOURISM & ARCHAEOLOGY

AZAD GOVT. OF THE STATE OF JAMMU & KASHMIR
Tourism Complex Bank Square Chatter, Muzaffarabad
Voice 05822-921421/921158/921317 Fax: 05822-921660

No.

Dated:

To,

M/S Pak Power Govt Contractor
14-Brandreth (Nishter) Road,
Lahore

Subject: **WORK ORDER FOR "ELECTRICAL WORK & HISTORICAL
ILLUMINATION OF RED FORT MUZAFFARABAD"**

With reference to your Bid received on 20-08-2020 regarding **"ELECTRICAL WORK & HISTORICAL ILLUMINATION OF RED FORT MUZAFFARABAD"** against tender notice published on AJK PPRA website. Your Bid has been accepted and you are hereby allowed to start execution the following Civil works. The Summary is as under.

SR.	DETAIL OF ITEMS	QUANTITY	UNIT	RATE	Total (In Rupees)
1	Supply at work, Installation, testing and commissioning of following outdoor type pad Mounted distribution transformers. i) 400 KVA	1	Each	2,265,000	2,265,000
2	Supply and Installation of 50KVA Generator with foundation including imported Super Silent Canopy, Imported ATS 100 Amp, Battery with Maintenance with all respect	1	Each	2,060,000	2,060,000
3	Supply and Installation of 60KVA Generator with foundation including imported Super Silent Canopy, Imported ATS 100 Amp, Battery with Maintenance with all respect	1	Each	2,250,000	2,250,000
4	Supply, Installation, testing and Commissioning of Air Conditioners Split Type with Power Breaker Size 1.5 Ton complete with all respect Earth with necessary flexible pipe and thimbles. 100 Amp	4	Each	97,000	388,000
5	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries, and repairing surface, etc., complete with all specials. i) 25 mm i/d	4600	RM	160	736,000
6	Supply and erection of PVC pipe for surface wiring (main and sub-main) including clamps, inspection boxes, pull boxes bends etc., complete with all specials: i) 50 mm i/d	1500	RM	200	300,000
7	Supply and erection of PVC pipe for surface wiring (main and sub-main) including clamps, inspection boxes, pull boxes bends etc., complete with all specials: i) 100 mm i/d	220	RM	418	91,960
8	Supply at work, Laying, testing and commissioning of following LT 600/1000V cable laid directly in already excavated trenches and provision of warning tape as per requirement, WAPDA specifications No. DDS 8:2007, standards provided in the given drawings, subject to the approval of the Project Manager. a) 300 mm ² 4-Core AI/PVC/PVC	530	RM	3209	1,700,770

2216
14-09-2020

[Handwritten signature]

[Handwritten signature]



THE DIRECTORATE GENERAL OF TOURISM & ARCHAEOLOGY

AZAD GOVT. OF THE STATE OF JAMMU & KASHMIR

Tourism Complex Bank Square Chatter, Muzaffarabad

Voice 05822-921421/921158/921317 Fax: 05822-921660

No.

Dated:

9	Supply, Installation, Testing and Commissioning of 95 mmsq (19/2.52") 4-core AL/PVC/PVC insulated, sheathed cable complete in all respect	320	RM	1,239	396,480
10	Supply, Installation, Testing and Commissioning of 70 mmsq (19/2.17") 4-core AL/PVC/PVC insulated, sheathed cable complete in all respect	590	RM	1,109	654,310
11	Supply, Installation, Testing and Commissioning of 50 mmsq (19/1.83") 4-core CU/PVC/PVC insulated, sheathed cable complete in all respect	580	RM	3,338	1,936,040
12	Supply, Installation, Testing and Commissioning of 25 mmsq 7/2.13 mm, 4-core CU/PVC/PVC insulated, sheathed copper cable complete in all respect	500	RM	1,565	782,500
13	Supply and install 16mm sq 7/1.63 mm (7/0.064") twin core PVC insulated, sheathed 600/1000v cable with Copper conductor directly clipped on wall etc power wiring.	1080	RM	451	487,080
14	Supply and install 6mm sq 7/1.12 mm (7/0.044") twin core PVC insulated, sheathed and multicore 600/1000v cable complete in all respect	885	RM	232	205,320
15	Supply and install 4mm sq 7/0.91 mm (7/0.036") twin core PVC insulated, sheathed cable complete in all respect	1450	RM	166	240,700
16	Supply and install 2.5mm sq 7/0.74 mm (7/0.029") twin core PVC insulated, sheathed cable complete in all respect	2300	RM	117	269,100
17	Supply, Installation, testing and commissioning of 3/0.029" (1.5mm sq) Single Core Cable complete in all respect	3300	RM	42	138,600
18	Supply, Installation, testing and commissioning of Wall Washer Light Fixture with Rust Resistant Casing complete in All respects i) 36 Watt	60	Each	9,544	572,640
19	Supply, Installation, testing and commissioning of Wall Mounted SMD/COB Flood Light with Rust Resistant Casing complete in All respects i) 70 Watt	70	Each	10,500	735,000
20	Supply, Installation, testing and commissioning of Wall Mounted SMD/COB Flood Light with Rust Resistant Casing complete in All respects i) 150 Watt	75	Each	19,500	1,462,500
21	Supply, Installation, testing and commissioning of Wall Mounted SMD/COB Flood Light with Rust Resistant Casing complete in All respects i) 100 Watt	50	Each	13,200	660,000
22	Supply, Installation, testing and commissioning of in ground lights complete in All respects (i) in ground light 6.5W (IP65)	155	Each	7,450	1,154,750
23	Supply, Installation, Testing & Commissioning of Pole Light(60 Watt)	75	Each	19,850	1,488,750
24	Supply and Installation of Street Light Poles (18 ft)	75	Each	22,000	1,650,000
25	Supply, Installation, Testing and Commissioning of Standard LED Energy Saver (23w), with Holder and Casing complete in All respects	26	Each	400	10,400
26	Supply, Installation, Testing and Commissioning of Wall Ceiling LED Light, 7W with Casing complete in all respect	20	Each	800	16,000
27	Supply and erection of electric energy meter, including meter 38.1 testing fee, etc. b) three phase, 4 wires: iii) 3x80 Amp, 400 volts	5	Each	6200	31,000



THE DIRECTORATE GENERAL OF TOURISM & ARCHAEOLOGY

AZAD GOVT. OF THE STATE OF JAMMU & KASHMIR
Tourism Complex Bank Square Chatter, Muzaffarabad
Voice 05822-921421/921158/921317 Fax: 05822-921660

No.	Dated:					
28		Supply Installation Testing and Commissioning of Ceiling Fan (56") complete in all respect	18	Each	4,000	72,000
29		Supply and Installation of wall Bracket Fan (26") complete in all respect	10	Each	3350	33,500
30		Supply and Erection of PVC Duct for Open Wiring 25mm x 25mm	3200	Rft	200	640,000
31		Supply Installation Testing and Commissioning of Light Plug (15-e20A) with back box Complete with all respects	42	Each	1300	54,600
32		Supply Installation Testing and Commissioning of Power Plug 32Amp eith back box Complete with all respects	39	Each	1500	58,500
33		Supply Installation Testing and Commissioning of Switch Plate 7" x 4" with 10 Switches and back boxes Complete with all respects	51	Each	1450	73,950
34		Supply Installation Testing and Commissioning of Switch Plate (4" x 4") with 2 Switches 2 sockets and back boxes Complete with all respects	28	Each	700	19,600
35		Supply, Installation Testing and Commission of Main LT Distribution Panel (Along with the Fixing of Timer relays, Outgoing Incoming Breakers MCs, Overload protection systems, and CTs including Dimmers for lights) Complete with all respects	1	Each	240,000	240,000
36		Supply, Installation Testing and Commissioning of SUB Distribution Box (Along with the Fixing of Timer relays, Overload protection systems, MCs and CTs) with powder Coated Casing Complete with all respects	14	Each	49,500	693,000
37		Supply and Install 10" (250mm) sweep Exhaust Fan including Plastic Louvers Complete with all respects	18	Each	2100	37,800
38		Hand Hole with Cover 12"x12"x12" complete in All respects	49	Each	4,000	196,000
39		Supply, Laying, Testing and Commissioning of Telephone 2 pair Copper Cable complete in All respects	700	RM	143	100,100
40		Supply, Laying, Testing and Commissioning of Cat 6 Copper Cable complete in All respects	850	RM	166	141,100
41		Supply, Installation, testing & Commissioning of Security Camera Night vision including CCTV Cameras, CCTV Dome Cameras, CCTV Test Monitor and Camera Tester, Wiring cables, DVR, Hard Disk, BNC video input device, Coax cables, Ethernet Cable, flat cables, RCA, F connectors, LED TV 45, Computer core i3, Wi-Fi Router, Switches.	30	Each	5000	150,000
42		Supply, Installation, testing & Commissioning of Security Walk Through Gate with Screening Equipment	1	Each	220,000	220,000
43		Supply, Installation, testing & Commissioning of Ticket Dispenser Machine for E Ticketing, Barriers, Ticket Printer with all respects	1	Job	1,195,000	1,195,000
Subtotal						26,608,050

1. It is pertinent to mention here that the payment will be made after deduction of all taxes.
2. All the terms and conditions will be same as per Contract document.
3. Specifications mentioned in tender documents will be followed.



THE DIRECTORATE GENERAL OF TOURISM & ARCHAEOLOGY

AZAD GOVT. OF THE STATE OF JAMMU & KASHMIR

Tourism Complex Bank Square Chatter, Muzaffarabad

Voice 05822-921421/921158/921317 Fax: 05822-921660

No.

Dated:

4. Time of Completion of the said work is 24 months.
5. If the above mentioned rates and conditions are accepted, you may come for the formal agreement along with the Letter of Acceptance.
6. The Details of execution works is Attached.


Admin officer,
Tourism & Archaeology,
AJ&K Muzaffarabad.

No. 7021-26

Dated: 10 / 09 / 20

Copy to:

1. PS to the Secretary tourism ,information and ITB, GoAJK for information please
2. The Accountant General GoAJK, Muzaffarabad.
3. PA to Director General Tourism, GoAJK ,Muzaffarabad for information
4. Director (C&P), WCLA, Lahore
5. The Deputy Director ,AJKPPRA S&GAD, GoAJK ,Muzaffarabad
6. The XEN Tourism and Archeology GoAJK ,Muzaffarabad


Admin officer, 10/9/2020
Tourism & Archaeology,
AJ&K Muzaffarabad.